

**CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY**  
(Council of scientific and industrial research)

**NAME OF WORK : Underground service connection to Animal House at CSIR-NEIST, Jorhat**

SI No	Particulars of the item	Qty	Unit	Rate in figures in	Rate in words	Amount in Rs.
1	Supplying and laying of 3.5 x 95 sq.mm size PVC insulated and sheathed 11 kV grade aluminium stranded armoured underground cable laid in ground/partially in air including excavation of cable trench up to 75cm depth refilling, protecting brick covering , sand cushion etc complete handling surplus soil in proper place and proper size of cable lug, cable arrow mark as specified and directed by department. (Havells/Finolex/Polycab Make)	261	Mtr			
2	Supply including fitting and fixing of 1.1 kV PVC/XLPE cable straight trough jointing Kits Raychem RPG Tubular Sleeve Version including all accessories for 120 sq.mm 3.5 core size UG cable including testing and commissioning as specified and directed by deptt.	2	Each			
3	Supplying and laying of 80 mm (3 inch) dia medium duty GI pipe complete with socket (Jindal Make) complete as required and specified by deptt.	9	Mtr			
4	Making good by damage done as directed by department		LS			
	<b>Total quoted amount in Rs.</b>					

Rupees :

Only

NB: Rate must be written both figures and words